



GENERAL NOTES:

- A. FOR STANDARD SYMBOLS AND NOMENCLATURE SEE DRAWINGS 50489-530-020-PID-1104.001 & .002.
- B. ALL EQUIPMENT NUMBERS SHOWN ON THIS P&ID ARE PRECEDED BY 530--.
- C. ALL INSTRUMENT NUMBERS SHOWN ON THIS P&ID ARE PRECEDED BY 030--.
- D. FOR TYPICAL INSTRUMENT CONNECTION SBDV, XV, MOV & ESDV DETAILS SEE DRAWINGS 50489-530-020-PID-1108.001, .002, .003, .004, .005, .006 & .007.
- E. FOR MISCELLANEOUS PIPING TYPICAL VALVING, DRAINAGE & GENERAL ARRANGEMENT OF LEVEL INSTRUMENTS, PUMPS, STRAINERS & CONTROL VALVES SEE DRAWINGS 50489-530-020-PID-1108.001 TO 1108.010.
- F. DRAWING NUMBERS SHOWN IN P&ID CONTINUATION BOXES ARE ABBREVIATED SHOWING DRAWING SEQUENTIAL NUMBERS ONLY. THE FULL FORM OF THE DRAWING NUMBER IS 50489-530-020-PID-XXXX.SHT.NO.
- G. FOR MATERIAL SELECTION DIAGRAM SEE DRAWINGS 50489-530-020-MSD-1001.001 TO 1023.
- H. DETAIL NUMBERING FOR CI, SC, CC & CP SEE DRAWING 50489-530-020-PID-1108.003.
- I. PAINTING & COATING ARE IN ACCORDANCE WITH KOC-P-001.
- J. LOW POINT DRAIN & HIGH POINT VENT ARE INDICATED IN P&ID.
- K. FOR CAUSE & EFFECT REFER DOC. NO. 50489-530-020-PHL-1009.
- L. FOR ALARM VALUES REFER DOC. NO. 50489-530-020-SUM-1006.

NOTES:

- 1. FLUSHING CONNECTION IS PROVIDED AT END OF COLLECTION HEADERS, AND AT ANY CHANGES IN DIRECTION OF UNDERGROUND PIPE OF 90°.
- 2. ADDITIONAL CLEANING FACILITIES ARE PROVIDED AT ANY CHANGES IN DIRECTION OF 45°, AND AT A MAXIMUM OF 50 METRE INTERVALS ON STRAIGHT RUN.
- 3. EQUIPMENT AND INSTRUMENT ISOLATION VALVES ARE SHOWN ON CONTINUATION P&IDs.
- 4. 4"-CO INDICATES CLEAN OUT FLANGE IN CONCRETE CLEAN OUT PIT.
- 5. DELETED.
- 6. SLOPE OF ALL THE BRANCH LINES, MAIN & SUB HEADERS ARE 1:200 IN THE DIRECTION OF FLOW.
- 7. TIE-IN FOR DRAIN LINES INTO SUB HEADER FROM BRANCH HEADER IS AT 45° IN THE DIRECTION OF FLOW.
- 8. ALL DRAIN PIPING SHOWN IN THIS P&ID IS LAID UNDERGROUND, EXCEPT IN CLEAN-OUT PIT.

AS-BUILT	
KOC APPROVAL	
NAME / KOC No:	
DESIGNATION :	
GROUP / TEAM :	
SIGNATURE :	
DATE :	

AS-BUILT	
LARSEN & TOUBRO LIMITED	
NAME :	VAIBHAV VERMA
DESIGNATION :	AGM
SIGNATURE :	
DATE :	07-Aug-2018
DEPT/ DIVISION :	ENGINEERING

Z0	ISSUED FOR AS-BUILT	BAK/SSI	AKG	SRA	RAK	07.08.18
01	ISSUED FOR CONSTRUCTION	BAK/SSI	AKG	SRA	RAK	12.12.16
0	ISSUED FOR CONSTRUCTION	PAK/CHS	AKG	SRA	RAK	28.04.16
D	ISSUED INCORPORATED CLIENT COMMENTS	HSR/CHS	AKG	SRA	RAK	18.03.16
C	ISSUED INCORPORATED CLIENT COMMENTS	JSI/VSA	AKG	SRA	RAK	04.12.15
0C	ISSUED INCORPORATED CLIENT COMMENTS	JSI/VSA	AKG	SRA	RAK	30.05.15
B	ISSUED INCORPORATED CLIENT COMMENTS	JSI/VSA	AKG	SRA	RAK	20.02.15
A	ISSUED FOR APPROVAL	JSI/ABY	AKG	SRA	RAK	11.12.14
REV.	DESCRIPTION	DRAWN	CHECKED	HOD APPRD.	PEM	DATE

CONTRACTOR REVISION

 KUWAIT OIL CO. K. S. C. <small>شركة نفط الكويت</small> <small>ش.م.ك.</small>	
CONTRACTOR DETAILS:- LARSEN & TOUBRO LIMITED FARIDABAD	
PROJECT TITLE:- NEW GATHERING CENTRE GC-30 IN NORTH KUWAIT	
DOCUMENT TITLE:- PIPING & INSTRUMENTATION DIAGRAM CRUDE AREA-II GRAVITY DRAIN SYSTEM HEADER	
PROJECT NO.	DRAWING NO.
CONTRACTOR DRG. NO.	REV. KOC DRG. NO.
50489-530-020-PID-1207.001	Z0
SHEET NO. 1 OF 3	SHEET NO.
COMPANY DRG. NO.	REV.
EF1902-530-DCO-PID-0207.001	A2
SHEET NO.	